

DALLASTOWN-YOE WATER AUTHORITY

AGENDA

May 10, 2023

I MEETING CALLED TO ORDER

II PLEDGE OF ALLEGIANCE

III ACTION ON 4/12/23 MEETING MINUTES

IV VISITORS

V ENGINEER'S REPORT

1. SR0074 (Hardees) Interconnect Project: All information that has been requested from CFA in support of the funding application submitted to the PA Small Water and Sewer Program has been provided to CFA by either Borough or HRG Staff. The PA DEP Public Water Supply Permit amendment remains in technical review. As part of the hydraulic modeling effort, we have worked with the Borough Staff to install pressure loggers at the meter station to provide information utilized to calibrate the model and perform fire flow analyses and simulations (further described below).
2. Park Street Tank: The Public Water Supply Permit for the installation of a new tank mixer has been issued by PA DEP and is attached to this month's agenda for reference. We have forwarded the approved Permit to I.K. Stoltzfus to ensure that all work which they quote to the Authority is performed in accordance with the Permit and its associated Special Conditions. Upon the receipt of updated quotes for the supply and installation of the new mixer equipment, the Authority can proceed with the proposed work. HRG will assist the Staff as needed in reviewing materials submittals and ensuring proper installation of the new equipment. We will also assist in any items to close out the Permit following installation and performance of testing required by the Special Conditions.
3. Water System Model: HRG assisted the Staff in performing fire hydrant flow testing at various locations throughout the Authority's system on April 21st. The results of the fire hydrant flow tests have been tabulated and are included as an attachment to this month's agenda for reference. We were informed that during the hydrant testing, Red Lion was flushing their system and work was being performed on the Hardees Interconnect, though the test data obtained is sufficient for performing calibration of the model. HRG also returned the data loggers to the Staff which have since been re-installed at each interconnection with Red Lion to gather operating data which will be utilized in performing model simulations. With flushing of the D-Y system expected to start on May 8th, we would like to gather data for at least one week of normal system operation after all flushing is completed and then utilize that data to perform the remainder of the modeling effort. Preliminary results of the project should become available in mid-June at the completion of all flushing activities.
4. 70 S. Franklin Subdivision: A sketch plan was received by the Authority prior to last month's meeting. We are awaiting the receipt of a formal Plan submission prior to performing additional services relative to this project.

VI SOLICITOR'S REPORT

- Verizon
- T-Mobile
- Other

VII MANAGER'S REPORT

- Tank Level Report
- Master Meter Reads
- Other

VIII ANY OTHER BUSINESS TO COME TO THE ATTENTION OF THE AUTHORITY

IX APPROVAL OF BILLS

X APPROVAL OF FINANCIAL STATEMENTS

XI ADJOURNMENT